BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED TENDER SCHEDULE –'B'

Name of Work::-Improvements of drain and asphalting to Someshwara temple 3rd main cross roads in ward No 04

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil invlving an average horizontal throw up to 2 meters and an average lift up to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no 138, PWD SR 2014-15)	Cum	285.76	75.60	Rupess seventy five and paise sixty only
2	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2014-15	Cum	403.54	264.60	Rupess two hundred sixty four and paise sixty ony
3	Providing and fixing Precast RCC Slabs as Per approved design, specification and Direction Engineer-in-Charge. (Approved Data Rate).	Sqm	58.85	1498.00	Rupess one thousand four hundred ninety eight only
4	KSRRB M409-17: Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification: 406 (PWD SR 2014-15 P.N.154 It 20.18)	Cum	79.23	1438.56	Rupess one thousand four hundred thirty eight and paise fifty six only
5	KSRRB M500-6,Providing and applying primer coat with S.S.bitumen emulsion on prepared surface of granular base such as WBM,WMM including cleaning of road surfase and spraying primer at the rate of .60kg/Sqm using mechanical means complete as per specifications. MORTH SpecificationsNo502 (ITEMNO21.6,Page no157,PWD SR 2014-15)	Sqm	396.13	35.21	Rupess thirty five and paise twenty only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
6	KSRRB 500-11: Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant 40 tonne capacity, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve the desired density, 50 / 75mm compacted thickness with 3.3% bitumen but excluding cost of primer / tack cost with lead upto 1km including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH chapter 5, With 80/100 grade bitumen, P No. 176 Item No. 21.11.1/ PWD SR 2014-15	Cum	19.81	6624.72	Rupess six thousand six hundred twenty four and paise seventy two only
7	KSRRB 500-1.2 : Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. Specification No. KRBS 500-2 MORT & H Specification No. P.No 157. 1.21.2)	Sqm	5575.00	3.02	Rupess three and paise two only
8	KSRB 15-17.5:Applying priming coat over new wood surface and/or wood based surfaces after preparing the surface after throughly cleaning oil,grease,dirt and forign matter,sand papering and knotting liquid wood filler,for varnish including cost of materials,labour,complete as per specificationsP.NO115/15.59)	Sqm	5075.00	33.48	Rupess thirty three and paise forty eight only
9	KSRRB M500-18.Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading,premixed with bituminous binder and filler, transporting the hot mix to work site.laying with a paver finisher to the required grade,levell and alignment, rolling withs mooth wheeled,vibratoryandtandemrollers to achievethe desired compactionas sperMORTHSpecificationclauseno508completeinallrespectscompleteasperspecifications.using 40-60 TPH capacity HMP with mechanical pavour grading -II (25-30mm) with 5% CRMB 55 grade (Itemno 21.21.5 Pageno 160 2014-15)	Cum	152.15	9998.64	Rupess nine thousand nine hundred ninety eight and paise sixty four only
10	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/ sand/kanker/ Moorum. KSRRB M100-1:Placing tipper at loading point,loading with front end loader.dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no 130, PWD SR 2014-15)	Cum	689.04	68.04	Rupess sixty eight and paise four only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.